


15-179-20494-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Sheridan County, Sec. 8 Twp. 7S Rge. 26 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C SW NE



Locate well correctly on above  
Section Plot

Lease Owner The Maurice L. Brown Co.  
Lease Name Nicholson Well No. 1  
Office Address 200 Sutton Place Bldg., Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry hole  
Date Well completed Dec. 11 1977  
Application for plugging filed (verbally) Dec. 11 1977  
Application for plugging approved (verbally) Dec. 11 1977  
Plugging commenced Dec. 11 1977  
Plugging completed Dec. 11 1977

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation Depth to top Bottom Total Depth of Well 4050'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Set 1st plug at 900' with 70 sacks  
2nd plug at 240' with 20 sacks  
3rd plug at 40' with 10 sacks  
Cemented with 50/50 posmix, 6% gel  
Plug was down at 9:30 a.m., December 11, 1977

RECEIVED  
STATE CORPORATION COMMISSION

DEC 22 1977

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

12-22-77

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jack L. Partridge, Ass't. Secretary-Treasurer (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature)

Jack L. Partridge

801 Union Center, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 1977

Sandra Richman

Sandra Richman

Notary Public.

My commission expires July 21, 1979



CONTRACTOR'S WELL LOG

OPERATOR: The Maurice L. Brown Co.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: Nicholson #1  
 LOCATION: C SW NE Section 8-7S-26W  
 Sheridan County, Kansas  
 SPUD DATE: December 3, 1977  
 COMPLETION DATE: December 11, 1977

0	290	Surface soil, sand & shale
290	928	Sand & shale
928	2313	Shale & sand
2313	2342	Anhydrite
2342	2770	Shale
2770	3005	Shale, sand & lime
3005	3145	Shale
3145	3467	Lime & shale
3467	3610	Shale & lime
3610	3905	Lime & shale
3905	4010	Shale & lime
4010	4050	Lime
	4050	Rotary Total Depth

Spud hole at 4:15 p.m., December 3, 1977. Drilled 290' of 12 1/4" hole. Ran 7 joints of 8-5/8" surface casing (23#) set at 285.90'. Cemented with 200 sacks common cement, 2% gel, 3% CaCl. Cement did circulate. Plug was down at 4:20 a.m., December 4, 1977.

T.D. 4050'. Set 1st plug at 900' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' with 10 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 9:30 a.m., December 11, 1977. State Plugger - Gilbert Balthazor.

SAMPLE TOPS:

Anhydrite 2313'  
 B/Anhydrite 2345'

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 22 1977

STATE OF KANSAS )  
 ) ss.  
 COUNTY OF SEDGWICK )

CONSERVATION DIVISION  
 Wichita, Kansas


12-22-77

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Nicholson #1, C SW NE Section 8-7S-26W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge,  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me the undersigned, a Notary Public, in and for the county and state aforesaid, as of this 21st day of December, 1977.



Sandra Richman  
 Sandra Richman, Notary Public