

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sheridan

County. Sec. 27 Twp. 7S Rge. 5 (E) 29 (W)

Location as "NE/CNW/SW" or footage from lines C NW SW

Lease Owner Braden Drilling, Inc. & Zenith Drilling Corp., Inc.

Lease Name Hill Well No. I-27

Office Address 1620 Wichita Plaza, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed October 5 1968

Application for plugging filed October 5 1968

Application for plugging approved October 5 1968

Plugging commenced October 5 1968

Plugging completed October 5 1968

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4225 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	322.81	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with 153 sacks cement

Plugged @ 1675' w/70 sacks

Plugged @ 340' w/20 sacks 50-50 Posmix with 6% Gel

Plugged @ 40' w/10 Sacks

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 - 1968

CONSERVATION DIVISION
Wichita, Kansas

10-09-1968

Name of Plugging Contractor Braden Drilling, Inc. (If additional description is necessary, use BACK of this sheet)

Address 1620 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss. James Tasheff

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Tasheff, Vice-President

1620 Wichita Plaza, Wichita, Kansas


October, 1968

Subscribed and Sworn to before me this 7th day of

My commission expires 1/19/69

Esther Lamone
Notary Public

Notary Public.



179
15-~~15~~-20145-00-00

DRILLER'S LOG


Braden Drilling, Inc. &
Zenith Drilling Corp., Inc.
1 Hill
C NW SW, Sec. 27-7S-29W
Sheridan County, Kansas

Commenced: September 28, 1968
Completed: October 5, 1968
Elevation: 2849 G.L.
2854 K.B.

8-5/8" Surface Casing 322.81 set @ 328' with 240 Sacks

<u>From</u>	<u>To</u>	<u>Formation</u>
0	280	Sand
280	329	Shale
329	1080	Shale - Shells
1080	1475	Shale
1475	2221	Shale & Sand
2221	2519	Shale
2519	2561	Anhydrite
2561	2980	Shale & Shells
2980	3165	Shale
3165	3520	Shale - Lime
3520	3880	Lime & Shale
3880	4225	Lime
4225		RTD

I hereby certify that this is a true and correct log of the above captioned well as shown by the daily drilling reports.


James Tasheff

Subscribed and sworn to before me this 7th day of October, 1968.




Esther Lamone, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 - 1968
CONSERVATION DIVISION
Wichita, Kansas