


OP

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Sheridan County, Sec. 25 Twp. 7S Rge. 29W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C NE NE NE  
Lease Owner Dean & Clark, Inc.  
Lease Name Hesterberg Well No. 1  
Office Address 416 Union Center Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed March 22, 1968  
Application for plugging filed March 22, 1968  
Application for plugging approved March 22, 1968  
Plugging commenced March 22, 1968  
Plugging completed March 22, 1968  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Box 157, Morland, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4220 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

From 20 feet below Base of Dakota at 1925 feet to 20 feet above Dakota at 1700', cemented with 100 sacks 50-50-Pozmix -6% Jel. At base of surface (300'), set wood plug, cemented with 20 sx. 50-50 Pozmix-6% Jel. Set wood plug at 40 feet, 1/2 sx. cottonseed hulls and 10 sx. cement. Job completed at 7:30 P.M. 3-22-68.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
05-24-1968


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dean & Clark, Inc.  
Address 416 Union Center Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Jay C. Clark (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay C. Clark  
Jay C. Clark  
416 Union Center Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of March, 1968



My commission expires August 30, 1969  
Phyllis Green  
Phyllis Green, Notary Public.

15-179-20079-00-00

RP

DRILLERS LOG

COMPANY: Dean & Clark, Inc.  
 CONTRACTOR: Company tools  
 LEASE NAME: Hesterberg No. 1  
 LOCATION: C NE NE NE, Section 25-7S-29W  
 Sheridan County, Kansas  
 ELEVATION: 2822' D.F. - 2825' K.B.  
 SURFACE CASING: 7 Jts. (288') 8-5/8"  
 COMMENCED: March 12, 1968  
 COMPLETED: March 22, 1968  
 ROTARY TOTAL DEPTH: 4220 feet

<u>FORMATION</u>	<u>DEPTH</u>	
Surface Soil-Sand-Shale	290	Spudded 12-1/4" hole at 10:00 A.M. 3-13-68 Drilled 12-1/4" surface hole to 290 feet. Set 8-5/8" surface casing (7-Jts.) at 288'. Cemented with 200 sacks common cement, plus 400# calcium. Cement circulated. Plug down at 3:00 P.M. 3-13-68.  DST #1: 3604-3653  No electric log run.  Plugged hole. Job completed at 7:30 P.M. 3-22-68
Shale	2170	
Shale-Shells	2475	
Shale	2521	
Anhydrite	2558	
Shale	2858	
Shale-Lime	2990	
Shale	3246	
Shale-Lime	3330	
Shale	3422	
Lime	4220	
RTD	4220	

<u>SAMPLE TOPS</u>	<u>DEPTH</u>	<u>DATUM</u>
Anhydrite	2521	+ 304
Tarkio	3644	- 819
Topeka	3732	- 907
Heebner	3937	-1112
Toronto	3961	-1136
Lansing	3974	-1149
Base Kansas City	4205	-1380
Rotary Total Depth	4220	-1395

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 24 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 )  
 COUNTY OF SEDGWICK ) ss:

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

Jay C. Clark  
 Jay C. Clark

Subscribed and sworn to before me this 29th day of March, 1968.

Phyllis Gillen  
 Phyllis Gillen, Notary Public

My commission expires; August 30, 1969

