

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-00588-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 36 Twp. 7 Rge. 23 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C SW NW

Lease Owner Burch Drilling Company, Inc.

Lease Name Jackson Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 1-15-62 19

Plugging completed 1-17-62 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3750 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	212'	None
				4-1/2"	3750'	3030'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3750', pushed plug to 3500' and ran 20' of sand. Dumped 4 sacks of @ 3480' with dump bailer. Pulled 3 jts. of 4 1/2" casing and pumped 31 sacks of mud @ 650', could not get circulation..Pulled 3 more joints of 4 1/2" casing and got circulation. Pumped in 20 sacks of cement. Pulled 4 1/2" casing to 180' and circulated with 20 sacks of cement. Left 1 jt. in and pumped in 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 25 1962
CONSERVATION DIVISION
Wichita, Kansas
1/25/62

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 1962

My commission expires May 20, 1964
Milton J. Volin Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


15-065-00588-02-00

Company- BURCH DRILLING COMPANY
Farm- Jackson No. 1

SEC. 36 T. 7 R. 23W
C SW NW

Total Depth. 3750'
Comm. 9-12-58 Comp. 9-21-58
Shot or Treated.
Contractor. Burch Drlg.
Issued. 5-9-59

County Graham
KANSAS



CASING:
8 5/8" @ 212' cem. w/160 sx.
4 1/2" @ 3750' cem. w/125 sx.

Elevation. 2289'

Production. 110 BOPD

Figures Indicate Bottom of Formations.

shale	470
shale & shells	1930
Anhydrite	1970
shale & shells	2000
shale	2320
shale & lime streaks	2575
shale & lime	3537
lime	3750 RTD
Total Depth	

TOPS: SCOUT	
Anhydrite	1930
Heebner	3497
Toronto	3522
Lansing	3539

Received:
1/25/1962