


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Fabricius, Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9 5/8	354.98	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

First plug set at 600 feet with 25 sacks cement.

Second plug set at 300 feet with 15 sacks cement

Last plug set at 10 feet with 10 sacks.

RECEIVED
STATE CORPORATION COMMISSION
SEPT 19 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

9/19/58

STATE OF TEXAS, COUNTY OF TAYLOR, ss.
Jack Stivers

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Jack Stivers
Vice President
P.O. Drawer 2040, Abilene, Texas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 19 58

My commission expires June, 1959

Shirley Madsen
Notary Public.

PLUGGING
FILE SEC. 18 T. 7 R. 37W
BOOK PAGE 128 LINE 33

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1958

Miami Petroleum Company, Inc.

CONSERVATION DIVISION
Oklahoma, Kansas

W. W. BEAR "C" # 1
Sherman County, Kansas

W. W. Bear "C" # 1
Section 18-T-7-S, R-37-W, Sherman County, Kansas

Date	Depth		Description of formation or type of work completed
	From	To	
8-25-58	0	184	Gray shale with sand streaks
	Spudded 8-25-58 Evening Tour Rig 3		
	Location SW/SW of Section 18, T-7-S, R-37-W, Sherman County, Kansas		
8-26-58	184	394	Gray shale with sand streaks
	Ran and cemented 354.98' (11 Joints) 9-5/8" surface casing with 250 sacks cement. Plug down 12:30 P.M. 8-26-58.		
8-27-58	394	1454	Gray shale and calcareous shale
		1575	Sand and calcareous gray shale
		1860	Calcareous gray shale with sand streaks
8-28-58	1860	2557	Gray shale with sand and lime streaks
		2584	Red shale
		2990	Red shale with anhydrite, lime and sand streaks
8-29-58	2990	3100	Red shale with anhydrite streaks
		3150	Salt and anhydrite
		3182	Anhydrite
		3693	Red shale with anhydrite, sand and dolomite streaks
8-29-58	3693	3699	Lime
		3780	Red shale with lime, sand, and anhydrite streaks
8-30-58	3780	3840	Red shale with lime streaks
		3904	Lime and gray shale streaks
		3946	Gray shale with lime streaks
		4039	Lime and gray shale streaks
8-31-58	4039	4328	Lime and gray shale streaks
		4334	Black shale
		4350	Gray shale and lime streaks
9-1-58	4350	4413	Gray shale and lime streaks
		4600	Chalky lime and gray shale streaks
		4650	Chalky lime with gray and black shale streaks
9-2-58	4650	4780	Chalky lime with gray shale streaks
		4861	Chalky lime with gray and black shale streaks
9-3-58	4861	4970	Chalky cherty lime with gray and black shale streaks
		5034	Varicolored shale with lime and conglomerate streaks
9-4-58	5034	5084	Varicolored shale with lime and conglomerate streaks
		5098	Shaley Conglomerate
		5121	Lime and chert
9-4-58	5121	5167	Lime with dolomite and chert streaks
		5172	Dolomite
9-5-58	5172	5290	Dolomite with lime and chert streaks
		5349	Lime with chert
9-6-58	5349	5446	Chalky lime with chert streaks
		5492	Dolomite
9-7-58	5492	5500	Dolomite T.D.
	Ran Schlumberger from 5499-358'		

PLUGGING			
FILE	SEC. 18	T. 7	R. 37W
BOOK	PAGE 128	LINE	33

15-181-00007-00-50

Miami Petroleum Company, Inc.

W. W. BEAR "C" # 1
Sherman County, Kansas (Cont'd)

Following is a list of the formations encountered in the W. W.
Bear "C" # 1

T/Anhydrite	3150' (347)	T/Marmarton	4717' (-1220)
T/Heebner	4328' (-831)	T/Cherokee	4852' (-1355)
T/Lansing Kansas City	4413' (-916)	T/Mississippian	5098' (-1601)
		T/Arbuckle	5446' (-1949)

This 8 day of Sept 1958.

Jean Steiers
Vice-President

MIAMI PETROLEUM COMPANY, INC.

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1958

CONSERVATION DIVISION
Wichita, Kansas

9/19/58

PLUGGING			
FILE	SEC. 18	T. 7	R. 37W
BOOK	PAGE 128	LINE	33