


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-163-01081-00-00
Form CP-4

NORTH



Locate well correctly on above
Section Plat

Rooks County, Sec. 29 Twp. 8 Rge. 16 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Kim Oil Company, Inc.
Lease Name Kollman Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 19 1963
Application for plugging filed May 19 1963
Application for plugging approved May 19 1963
Plugging commenced May 19 1963
Plugging completed May 19 1963
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	245'	Cmtd w/210 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill w/heavy mud to 600'
Set bridge plug @ 600'
Dump 20 sax cement on plug thru 4 1/2" drill pipe
Fill w/heavy mud to 240'
Set bridge plug @ 240'
Dump 20 sax cement on plug thru 4 1/2" drill pipe
Fill w/heavy mud to 40'
Set bridge plug @ 40' w/1/4 sax hulls on plug
Dump 10 sax cement on plug to cellar

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1963

CONSERVATION DIVISION
Wichita, Kansas

7/12/63

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Shields Drilling Company, Inc.
Address Shields Bldg., Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
I, J. L. Spurgeon, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Spurgeon
Box 468, Russell, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July 1963

My commission expires April 4, 1967, Jude A. Schack Notary Public.



Shields

15-163-01081-00-00
Russell, Kansas

WELL LOG

Operator. Kim Oil Company, Inc.
Well Kollman #1
Commenced May 12, 1963
Completed May 19, 1963
Contractor: Shields Drilling Company, Inc.

Well Description

C SW NE
Sec. 29-8S-16W
Rooks County, Kansas



Elevation:

Treatment:

Production:

D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	245'	Cmtd w/210 sax

Figures Indicate Bottom of Formations

Surface soil, shale, shells & sand	1,045'
Shale & Shells	1,235'
Anhydrite	1,272'
Shale	1,605'
Shale & lime	1,920'
Lime	2,345'
Shale & lime	2,870'
Lime	3,450' RTD

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1963

CONSERVATION DIVISION
Wichita, Kansas

7/12/63

Notes