

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-02979-00-00

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 110-40 County: Rooks

Location: SW SE NE Sec. 18 Twp. 8 Rge. 16 (E) (W)

Name of Field: _____ Total Depth: 3210

I have this date completed supervision of plugging of:

Lease Name: Csesney Well No. A-1

Operator's Full Name: Herndon Drg Co

Complete Address: c/o West Supply Co Box 506 Chase, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No _____

If yes how long? _____ Reason: _____

Operation Completed: Hour 8PM Day 11 Month 7 Year 58

The above well was plugged as follows:

8 5/8" at 190' circulated with cement - 5 1/2" 3175' with 200 sax

cement behind - P. B. to 3000', perforated 3054'

Filled with sand to 3045', set 4 sax cement with dump bailer, pulled

2193' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" (Gel),

displaced 20 sax cement through 5 1/2" at 500', heavy mud to 180', displaced

20 sax cement through 5 1/2" at 180', heavy mud to 55', set rock and 10

sax cement to bottom cellar.

Signed: Edon Peety
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

PLUGGING
FILE SEC 18 T 8 R 16W
BOOK PAGE 110 LINE 40

7-19-58
RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1958
CONSERVATION DIVISION
Wichita, Kansas