

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

V

API Number 15-141-20,118-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Midea Exploration, Inc.

Complete Address 411 Farmers and Bankers Bldg., Wichita, Kansas 67202

Lease Name Knelling Well-No. 1

Location C SW NW Sec. 36 Twp. 8 Rge. 15 (~~East~~) (West)

County Osborne Total Depth 3875'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. and Allied Cementing Co., Inc.

Address 801 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour: 9:30 AM Day: 23 Month: October Year: 1981

Plugging Operations attended by Agent?: All Part _____ None _____

8 3/4" - 245 - Circ - Etc. 1888 KB No Hydrate

The above well was plugged as follows:

Hole circulated and filled with mud. 50 sacks cement pumped through drill pipe at 900'. 50 sacks cement pumped through drill pipe at 310'. Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement.

Cement used 50-50 Pozmix w/2% gel 3% cc.

RECEIVED
STATE CORPORATION COMMISSION
10-26-81
OCT 26 1981

CONSERVATION DIVISION
WICHITA, KANSAS

I hereby certify that the above plugging instructions were given as stated herein

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 11-24-81

INV. NO. 8403-W