

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Building  
Wichita, KS 67202

API Number 15-163-21, 773

00-00

M/c-5267

Operator's Full Name H. & E. PETROLEUM, INC.

Complete Address 300 <sup>Hardage</sup> 816 UNION CENTER WICHITA, KANS. 67202

Lease Name HOLLMAN Well No. #1 "A"

Location W 1/2 - NW - SW Sec. 17 Twp. 8 Rge. 16 (East)(West)

County ROOFS. Total Depth 3208 FT

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ABERGROMBIE DRILLING M/c #179 (Harold Moley)

Address 801 UNION CTR. WICHITA, MS. 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 5:30 AM Day: 19 Month: SEPT Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 1141 FT SR. QUC W/450 5<sup>th</sup> 60% Pozmix - 2% GEL - 3% CA-CL (ALLIED CMA) BY.  
ORDERED 140 5<sup>th</sup> 50% Pozmix 6% GEL - 3% CA-CL AND 8 5/8" PLUG.  
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.  
1<sup>st</sup> Plug @ 1140 FT W/70 5<sup>th</sup> CMT.  
2<sup>nd</sup> Plug @ 270 FT W/40 5<sup>th</sup> CMT.  
3<sup>rd</sup> Plug - Solid Bridge @ 40 1/2 W/10 5<sup>th</sup> CMT.  
10 5<sup>th</sup> IN RAT HOLE (CIRCULATE)

CEMENTED BY ALLIED CMA.

Amount of Surface Casing: 1141 FT

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Marion Schmidt  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 27 1982

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICED

DATE 10-20-82

WV. NO. 1408-W

9-27-82

♡