

KANSAS

AL STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20144-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1968
CONSERVATION DIVISION
Wichita, Kansas
11-12-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Tilco, Et al

Complete Address: 815 Wichita Plaza Wichita, Kansas

Lease Name Kollman Well No. 1

Location NW SE NW Sec. 20 Twp. 8 Rge. 16 (E) (W) X

County Rooks Total Depth 3285

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Leben Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 12 N Day 8 Month 11 Year 1968

The Above well was plugged as follows:

RTD 3285' 8 5/8 csg set at 209' ewc Cmt mat 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leo J. Massey*
Well Plugging Supervisor

DATE 11/12/68

INV. NO. 8801-W