

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20392-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas
10-12-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Inc.
Complete Address 801 Union Center Wichita, Kansas 67202
Lease Name Gager Well No. 1
Location SE SE SE Sec. 20 Twp. 8 Rge. (E) (W) 16
County Rooks Total Depth 3383'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 2 P Day 5 Month 10 Year 1971

The above well was plugged as follows:
6 3/4 hole below surface.

RTD 3383' 8 5/8 csg set at 235' cwc 150 sk Cmt Mat 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 650' and displaced 60 sk
cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Messing
Well Plugging Supervisor

DATE 10-12-71
INV. NO. 4452-W