

KANSAS

20
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1968
CONSERVATION DIVISION
Wichita, Kansas

15-141-20010-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

8-19-68

Operator's Full Name Neven H. Veil VEIL

Complete Address: 1401 McKinley Great Bend, Kansas

Lease Name Bliss Well No. ~~3998~~ /

Location C SE SE Sec. 30 Twp. 8 Rge. 13 (E) (W) X

County Osborne Total Depth 3998

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Peel Bros. Inc.

Address: Hosington, Kansas License No.

Operation Completed: Hour 11:30 A Day 15 Month 8 Year 1968

The Above well was plugged as follows:

RTD 3998' 8 5/8 csg set at 226' cwc. Cem. Mat. 100 sx 50-50 poz cmt. W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cmt.
thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/19/68
INV. NO. 8306-U

Signed: Geo. Massey
Well Plugging Supervisor