


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County. Sec. 8 Twp. 8 Rge. 17 (~~E~~) (W)
Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner Murfin Drilling Company, etal
Lease Name TURNER "B" #1 Well No. _____
Office Address 507 Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-16-54 19_____
Application for plugging filed 2-16-54 19_____
Application for plugging approved 2-16-54 19_____
Plugging commenced 2-16-54 19_____
Plugging completed 2-16-54 19_____
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3363 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	159'	None
				5 1/2"	3342	2856

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with crushed rock from 3353' to 3330'.
Dumped 4 sacks cement with dump bailer, at 3330'.
Top of cement, 3305'. Pumped 35 sacks mud and 75
sacks cement with Sun Cementing Company to plug
well.

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1954
APR 23 1954
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Murfin Drilling Company Miller Casing, Pulling Company
Address 507 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. R. Murfin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WR Murfin
507 Union National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of April, 19 54

Edna Siemens
Notary Public.

My commission expires 7-20-57

PLUGGING
LINE SEC 8 T 8 R 17W
DATE APR 23 1954

WELL LOG

COMPANY Murfin Drilling Company, etal

SEC. 8 T. 8 R. 17W


FARM TURNER "B" #1 NO.

LOC. Rooks

NE NW NW

TOTAL DEPTH 3363
COMM. 2-6-54 COMP. 2-16-54
SHOT OR TREATED
CONTRACTOR Murfin Drilling Company
ISSUED

COUNTY KANSAS



CASING
20 10
15 8 5/8" 159'
12 6
13 5 1/2" 3342

ELEVATION 1886 R.B.

PRODUCTION D-A

FIGURES INDICATE BOTTOM OF FORMATIONS

495 Shale, Shells
560 Sand, Shale
640 Red Rock, Shale
725 Shale, Shells
945 Sand
1240 Red Bed
1275 Anhydrite
1595 Shale, Shells
1700 Salt, Shale
1845 Shale, Shells
2000 Shale, Lime, Shells
2335 Shale, Lime
2400 Lime, Shale
2745 Shale, Lime
3050 Lime, Shale
3161 Lime
3348 Lime, Shale
3348 R. T. D.

TOPS

Topeka 2797 - 911
Heebner 3007 - 1121
Toronto 3032 - 1146
L.K.C. 3052 - 1166
B.K.E. 3267 - 1381
Arbuckle 3340 - 1454
R. T. D. 3348 - 1462
Cable T. D. 3363

PLUGGING
FILE NO. 8 T 8 R 17 W
BOOK PAGE 23 LINE 25

RECEIVED
STATE CORPORATION COMMISSION
APR 23 1954
APR 23 1954
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of SEDGWICK } ss:

I, W. R. Murfin of the MURFIN DRILLING Company

upon oath state that the above and foregoing is a true and correct copy of the log of the TURNER "B" #1 well.

W. R. Murfin

Subscribed and sworn to before me this 16th day of April 19 54.

My Commission Expires: 7-20-57

Edna Siemens
NOTARY PUBLIC