


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 16 Twp. 8S Rge. 17E/W
Location as "NE/CNW1SW1" or footage from lines _____
SE NW NE
Lease Owner F & M Oil Company
Lease Name SCHINDLER Well No. #1
Office Address 422 Union Center, Wichita, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole
Date Well completed 06-14 1980
Application for plugging filed 06-14 1980
Application for plugging approved 06-14 1980
Plugging commenced 06-14 1980
Plugging completed 06-14 1980

Reason for abandonment of well or producing formation _____
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes _____

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3442'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

TD 3442'
Set 1st plug and 740' with 60 sx.
2nd plug set at 300' with 30 sx.
3rd plug set at 40' solid bridge with 10 sx.
rathole with 5 sx. Cemented with 50/50
posmix cement, 6% gel
Plug was down at 10:00 a.m., 06-14-80.

RECEIVED
STATE CORPORATION COMMISSION
JUL - 7 1980
JUL 7 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form)
Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
(employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Patrick
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of July, 1980.

My commission expires _____
SHERIE L. BROOKS
Sedgwick County, Ks.
My Appt. Exp. 8-21-82

Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR: F & M Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: SCHNEIDER #1
 LOCATION: SE NW NE, Section 16-8S-17W
 Rooks County, Kansas
 SPUD DATE: 06-09-80
 COMPLETION DATE: 06-14-80

0	40	Post Rock
40	310	Sand, Shale & Post Rock
310	1075	Shale
1075	1279	Shale & Sand
1279	1312	Anhydrite
1312	1562	Shale & Sand
1562	2955	Shale
2955	3442	Shale & Lime
	3442	Rotary Total Depth

Spud 5:00 p.m. 06-09-80. Drilled 310' - 12½" hole, ran 7 jts. of 8-5/8" - 20# (tally 301) set 308 RTD. Cemented with 240 sacks of common cement, 3% cc., 2% gel. Cement did circulate. Plug was down at 12:30 a.m. 06-09-80.

T.D. 3442'. Set 1st plug at 740' with 60 sx., 2nd plug at 300' with 30 sx., 3rd plug at 40' solid bridge with 10 sx., rathole with 5 sx. Cemented with 50/50 posmix, 6% gel. Plug was down at 10:00 a.m., 06-14-80.

SAMPLE TOPS:
 Anhydrite 1279'
 B/Anhydrite 1312'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)


RECEIVED
 STATE CORPORATION COMMISSION
 JUL - 7 1980
 JUL - 7 1980
 CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SCHNEIDER #1, SE NW NE, Section 16-8S-17W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 1st day of July, 1980.

 **SHERRIE L. BROOKS**
 Sedgwick County, Ks.
 My Appl. Exp. 2-21-82

Sherrie L. Brooks
 Sherrie L. Brooks, Notary Public