

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rooks County. Sec. 16 Twp. 8S Rge. ~~X(2)~~ 17 (W)

Location as "NE/CNW/SW" or footage from lines SE SW NE
Lease Owner Pickrell Drilling Company
Lease Name Schnidler "A" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 4 1971
Application for plugging filed April 4 1971
Application for plugging approved April 4 1971
Plugging commenced April 4 1971
Plugging completed April 4 1971
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3435 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	241'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug @ 720' w/70 sacks, Middle Plug @ 240' w/20 sacks
Top Plug @ 40' w/10 Sacks Cement.


RECEIVED
STATE CORPORATION COMMISSION
APR 12 1971
CONSERVATION DIVISION
Wichita, Kansas
APR 12 1971

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 7th day of April, 1971



Esther Lamone
Notary Public.

My Commission expires January 19, 1973

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 3/26/71

Rotary Drilling Completed 4/4/71

LOCATION: Schindler "A" No. 1, SE SW NE Section 16-8S-17W,
Rooks County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 12 Jts. 8-5/8" Surface Casing set @ 241' KB. Cemented with
140 sacks. Completed 7:45 P.M. Circulated.

No oil string run. D & A, Plugged 2:00 P.M. April 4, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

95	Post Rock		
241	Shale & Shells		
590	Shale	<u>C.F.S.</u>	
1292	Shale & Sand	2850	3398
1322	Anhydrite	3052	3407
1870	Shale	3200	3410
2065	Shale & Lime & Shale	3243	3415
2480	Shale & Lime	3260	3420
2635	Lime & Shale	3276	3425
2790	Shale & Lime	3370	3430
2970	Sandy Lime & Shale	3382	3435
3030	Shale & Lime	3390	
3052	Lime		
3122	Lime & Shale		
3220	Lime	<u>S.L.M.</u>	
3243	Lime & Shale	Board	3074.19
3270	Shale	Strap	3073.73
3276	Lime		.46 Difference
3390	Lime & Shale		
3402	Lime	<u>Slope Tests</u>	
3410	Arbuckle	2000	
3435	RTD	2500	
		3000	

RECEIVED
STATE CORPORATION COMMISSION
APR 12 1971
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 7th day of April, 1971, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts

to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamone
Esther Lamone Notary Public

