

15-163-19112-00-00

API NUMBER 5-22-52

LEASE NAME Arndts

WELL NUMBER 1

SPOT LOCATION NE NW NW

SEC. 9 TWP. 8 RGE. 17 (E) of (11)

COUNTY Rooks

Date Well Completed 5-22-52

Plugging Commenced 4-19-90

Plugging Completed 4-19-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 3381

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	106	8 5/8		None
	Casing	0	3380	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Shot 2 holes at 1375 and 2 holes at 825'
Mix 60 sks. 65/35 pos. 10% gel, 1/4# selflake per sk. 200# hulls. Pull 25 its. to 746 90. Mix 30 sks. 65/35 pos. 10% gel, 1/4# selflake per sk. 10H with tubing. Hook up to 5 1/2. Pumped 235 sks. 65/35 pos. 10% gel, 1/4# selflake per sk. at 1000#. Shut in 300#. Hook to annulus. Pump 1 bbl cement coming out of ground in bottom of cellar. Shoot 2 holes at 105'. Mix 25 sks. circulate cement out of 8 5/8.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245
 Address Box 723 Hays, Kansas 67601

BJ Titan cementer

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Ted Crawford

(Address) Box 723 Hays, Mo 67601

SUBSCRIBED AND SWORN TO before me this 23 day of April, 19 90

Rosemary Smith
 Notary Public

My Commission expires: APR 24 1990 5-1-1991



APR 24 1990
 CONSERVATION DIVISION
 Wichita, Kansas