

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,561-0-00

LEASE NAME Head

WELL NUMBER 1

SPOT LOCATION 940' FWL 380' FNL

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

NW/4 SEC. 10 TWP. 8S RGE. 17 (W)

LEASE OPERATOR Petroleum Management, Inc.

COUNTY Rooks

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208

Date Well Completed 12/2/84

PHONE # (316) 686-7287 OPERATORS LICENSE NO. 5242

Plugging Commenced 12/2/84

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/2/84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? Attached If not, is well log attached? Well log was not run.

Producing formation _____ Depth to top _____ bottom _____ T.D. 3544'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	365'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Cemented w/210 sx 50/50 Pozmix, 6% gel, 3% CaCl. Plug down @ 9:15 PM on 12/2/84
1st plug set @ 3400' w/25 sx. 4th plug set @ 360' w/40 sx.
2nd plug set @ 1300' w/25 sx. Rathole w/10 sx.
3rd plug set @ 765' w/100 sx & 1 sk Flocele
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____
Address Box 31 Russell, KS 67665


STATE OF Kansas COUNTY OF Sedgwick, ss. STATE CORPORATION COMMISSION

RECEIVED
JAN 29, 1985
JAN 29 1985

Bonnie Brown (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) Bonnie Brown
(Address) 400 N. Woodlawn, Suite 201
Wichita, KS 67208



SUBSCRIBED AND SWORN TO before me this 21st day of January, 1985

My Commission expires: 3-22-87

Jane Augustine
Notary Public