


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 17 Twp. 8 S Rge. 17 (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW SW NE  
Lease Owner Herndon Drilling Company  
Lease Name Schindler # 1 B Well No.  
Office Address Drawer 489, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed April 25 19 51  
Application for plugging filed April 26 19 51  
Application for plugging approved April 26 19 51  
Plugging commenced May 2 19 51  
Plugging completed May 2, 19 51  
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Elden Setty  
Producing formation Depth to top Bottom Total Depth of Well 3474 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 350 ft.  
Drilled hole @ 350 ft. Placed 15 sacks of cement in  
hole. Filled hole with mud to 10 ft below collar.  
Cased hole 10 ft below collar and filled with  
cement to bottom of collar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Herndon Drilling Company,  
Address P.O. Drawer 489, Tulsa, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
W. G. PRATHER (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.  
(Signature) W. G. Prather

SUBSCRIBED AND SWORN TO before me this 21 day of May, 1951.  
My commission expires Sept. 19, 1952.  
Notary Public.

RECEIVED  
MAY 22 1951  
STATE CORPORATION COMMISSION  
DIVISION  
17 8 17W  
BOOK PAGE 79 LINE 34

WELL LOG ON SCHINDLER "B" #1

Spudding date: 4-13-51

Date casing set: D & A

Date rotary completed: 4-25-51

Date cable completed:

Location:

SW SW NE Sec. 17-8S-17W  
Rooks County, Kansas

FROM	TO	FORMATION	REMARKS
0	30	Surface soil and rock	Ran 1 Jt. 13-3/8" Casing (used)
30	570	Shale and shells	at 28' w/50 Sx. Portland cement.
570	800	Shale	
800	1275	Shale and shells	
1275	1305	Anhydrite	
1305	1560	Red Bed and shells	Ran 32 Jts. 1280' <sup>8 7/8"</sup> 2' guide shoe new spiral weld casing at
1560	1900	Shale and shells	1285' w/600 Sx. cement
1900	1925	Shale, shells and lime	
1925	2215	Shale and lime	
2215	2365	Shale and shells	
2365	2815	Shale and lime	
2815	3474	Lime	
3474		TOTAL DEPTH	15 Sx. plug at 250' 10 Sx. plug at Surface

RECORDED  
STATE CORP.  
MAY 22 1951  
CONSERVATION DIVISION  
Wichita, Kansas  
*May 22, 1951*

Subscribed and sworn to before me this 9th  
day of May, 19 51.

I certify the above and foregoing to be a true and exact  
copy of the original driller's log on the Schindler "B" #1

*Edward Sturgeon*  
Notary Public  
My commission expires: Aug. 28, 1951

**PLUGGING**  
FILE SEC DT 8 R 17W  
BOOK PAGE 79 LINE 34

HERNDON DRILLING COMPANY  
*W. Moore*  
By: \_\_\_\_\_  
Title: \_\_\_\_\_