


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 12 Twp. 8 Rge. 17 (W)

Location as "NE/CNW/SW" or footage from lines. NE NE NW
Lease Owner Alkay Oil Company (A. H. Kasishke)
Lease Name Carrie Houston Well No. 1
Office Address 611 Kennedy Building, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 1 1954
Application for plugging filed October 1 1954
Application for plugging approved October 1 1954
Plugging commenced October 1 1954
Plugging completed October 1 1954
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation Arbuckle Depth to top Bottom Total Depth of Well 3436 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8 7/8" Surface Casing	Cemented	@ 180'	W/135 Sacks	Cement,	
	Circulated to top					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 180'
Set Plug @ 180'
Cemented with 20 Sacks Cement
Mudded up to 40'
Set Plug @ 40'
Cemented with 10 Sacks Cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke & Wood Drilling Company
Address Great Bend, Kansas


STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
E. G. Moehlenkamp, Office Manager (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. G. Moehlenkamp
611 Kennedy Building
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of October, 1954

D. Rene Stark
Notary Public.

My commission expires 3-28-57



007-511954

ALKAY OIL COMPANY
611 KENNEDY BUILDING
TULSA 3, OKLA.

COMPANY - Alkay Oil Company
FARM - Houston #1.

SEC. 12 T. 8S R. 17W
NE NE NW

TOTAL DEPTH - 3436
COMM. - 9-20-54 COMP. - 10-1-54
CONTRACTOR - Duke & Wood Drilling Company
ISSUED - 10-7-54

COUNTY - Rooks

ELEVATION - 1937 DF

PRODUCTION - D & A

CASING RECORD

8 5/8" - Set @ 180'

Figures Indicate Bottom of Formations

Surface Rock & Sand	70
Clay	91
Shale & Clay (Lime Stone)	95
Blue Shale	178
Lime Stone	185
Blue Shale	295
Shale & Dakota Sand	550
Shale & Clay-Sand Streaks	795
Sane & Shale Streaks	915
Red Bed	1223
Anhydrite	1258
Shale & Shell	1790
Shale, Shell, Lime Streaks	1910
Lime & Shale	2275
Lime	2395
Lime & Shale	2770
Lime	2840
Lime	3380
Lime, Shale & Chert	3413
Lime - Arbuckle	3436

TOFS:

Anhydrite	1223
Topeka	2801
Heebner	3015
Lansing	3058
Base Kansas City	3305
Conglomerate	3385
Simpson	3402
Arbuckle	3410
Total Depth	3436

STATE OF OKLA. DEPARTMENT OF GEOLOGY

OCT 8 1954
CONSERVATION DIV.
Wichita, Ks.

PLUGGING
FILE SEC. 12 T. 8 R. 17W
BOOK PAGE 68 LINE 32