

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

MAR 06 2006

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Kerr-McGee Westport Oil And Gas Company LP
Address: 5735 Pineland, Ste. 300 Dallas TX 75231
Phone: (214) 692-1800 Operator License #: 33002
Type of Well: Oil 3-7-06, PKT, Peroper. Linda
The plugging proposal was approved on: 2-7-06
by: Ken Jehlik (KCC District Agent's Name)
Is ACO-1 filed? [X] Yes [] No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-187-20689-00-02
Lease Name: Uney
Well Number: 24-1
Spot Location (QQQQ): - E-W/2 - NW
1200 Feet from [X] North / [] South Section Line
660 Feet from [] East / [X] West Section Line
Sec. 24 Twp. 29 S. R. 41 [] East [X] West
County: Stanton
Date Well Completed: 11-5-93
Plugging Commenced: 2-13-06
Plugging Completed: 2-14-06

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Surf and Prod formations with casing sizes like 20, 8 5/8, 5 1/2 and depths like 40, 1653, 5596, 850.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.


Mixed 500 lb. hulls to 50 sx cmt. to plug perfs from 4507 to 4107, pumped 58 bbls mud spacer to 1700, mixed 25 sx plug 1700 to 1500, 35 bbls mud to 0. (TOC on 5 1/2 @ 900) Shot to pull 5 1/2 to 600. Circ hole w/ mud 40 sx 600 to 480 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: KERR-MCGEE OIL & GAS ONSHORE LP formerly Westport Oil & Gas Company LP
State of TEXAS County, DALLAS, ss.

Linda Gruver, Sr Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Linda Gruver
(Address) 5735 Pineland, Suite 300, Dallas, TX 75231

SUBSCRIBED and SWORN TO before me this 2nd day of March, 2006
Notary Public My Commission Expires: 12/09/08



Market - Room 2078, Wichita, Kansas 67202