

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 035-22401 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud date 12-13-79

Well Operator: Gen-Dor Oil Company KCC License #: 9576  
(Owner / Company Name) (Operator's)

Address: 8135 281st rd City: Cambridge

State: Kansas Zip Code: 67023 Contact Phone: ( 620 ) 467 - 2615

Lease: Hann "B" Well #: 4 Sec. 15 Twp. 31 S. R. 3  East  West

C - NE - NW Spot Location / QQQQ County: Cowley

660 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: none Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 205 Cemented with: 85 Sacks

Production Casing Size: 5 1/2 Set at: 3134 Cemented with: 140 Sacks

List (ALL) Perforations and Bridgeplug Sets: perfs are from 3076 to 3084 (13 holes)

Elevation: 1246 ( G.L. /  K.B.) T.D.: 3134 PBTD: 3125 Anhydrite Depth: unknown  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): fill bottom of well with gravel to 50 feet above the perfs and dump bael 6sx of cement on top of the gravel, shoot off casing and pull it out of the well bore and circulate cement from a depth to surface as required by the Kansas Corporation Commission

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: ( Ron Whiteman cell # 620-222-4316 )

Brent Whiteman (home # 620-394-2841) cell # >>>> Phone: ( 620 ) 222 - 7808

Address: 3777 251st rd City / State: Atlanta, Kansas 67008

Plugging Contractor: Gen-Dor Oil Company KCC License #: 9576  
(Company Name) (Contractor's)

Address: 8135 281st rd, Cambridge Kansas 67023 Phone: ( 620 ) 467 - 2615

Proposed Date and Hour of Plugging (if known?): someone will call in when we are ready to commence plugging of the well

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: Feb 20th 2006 Authorized Operator / Agent: Brent Whiteman (owner)  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
FEB 22 2006  
KCC WICHITA

DRILLERS LOG

DEC 28 1979

OPERATOR: Brunson-Spines; 525 Fourth Financial Center; Wichita, Ks. 67202  
CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name \_\_\_\_\_ Hand \_\_\_\_\_ Well No. B4 \_\_\_\_\_

Sec. 15 T. 31 R. 3E Spot. CNE NW \_\_\_\_\_

County Cowley State Kansas Elevation \_\_\_\_\_

Casing Record:

Surface: 8 5/8" @ 205' with 85 Sxs.

Production: 5 1/2" @ 3134' with 140 Sxs.

Type Well: Oil Total Depth 3135' KB \_\_\_\_\_

Drilling Commenced: 12/13/79 Drilling Completed 12/18/79 \_\_\_\_\_

| Formation   | From | To   | Tops |
|-------------|------|------|------|
| Cellar      | 0    | 7    |      |
| Lwme, Shale | 7    | 2000 |      |
| Sand, Shale | 2000 | 2270 |      |
| Shale       | 2270 | 2535 |      |
| Lime        | 2535 | 2758 |      |
| Lime, Shale | 2758 | 2792 |      |
| Shale       | 2792 | 2853 |      |
| Lime        | 2853 | 2972 |      |
| Shale       | 2972 | 3013 |      |
| Lime, Shale | 3013 | 3060 |      |
| Shale, Sand | 3060 | 3135 |      |

RECEIVED  
FEB 22 2006  
KCC WICHITA

COMPLETION RECORD

Liner Record: Size \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_

Cementing Record: \_\_\_\_\_ Sacks \_\_\_\_\_

Perforating Record:

| Formation | Perforated Interval | Number Shots |
|-----------|---------------------|--------------|
| _____     | _____               | _____        |
| _____     | _____               | _____        |
| _____     | _____               | _____        |
| _____     | _____               | _____        |

Initial Production: \_\_\_\_\_

Electric Log \_\_\_\_\_ Type and Depths Covered \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Whiteman, Ron dba Gen-Dor Oil Co.  
8135 281st Rd  
Cambridge, KS 67023

February 27, 2006

Re: HANN B #4  
API 15-035-22401-00-00  
NENW 15-31S-3E, 660 FNL 3300 FEL  
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000