

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

Lease Operator: Vincent Oil Corporation  
 Address: 125 N. Market, Suite 1075 Wichita, Kansas 67202  
 Phone: (316) 262-3573 Operator License #: 5004  
 Type of Well: dry Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 2-13-06 (Date)  
 by: Herb Deines (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
none - dry hole Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 137-20446-0000  
 Lease Name: Schuck  
 Well Number: 1-32  
 Spot Location (QQQQ): \_\_\_\_\_ - SE - SW - NW  
2270 Feet from  North /  South Section Line  
920 Feet from  East /  West Section Line  
 Sec. 32 Twp. 5 S. R. 22  East  West  
 County: Norton  
 Date Well Completed: 2-13-06  
 Plugging Commenced: 2-13-06  
 Plugging Completed: 2-13-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	301'	8 5/8 in.	301'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

25 sx @ 2025', 100 sx @ 1225', 40 sx @ 355', 10 sx @ 40', 15 sx in Rathole and 10 sx in Mousehole. 200 sx total of 60/40 poz, 6% gel and 1/4# Flo-seal per sx. Plug down 10:30 pm on 2-13-06

Name of Plugging Contractor: WW Drilling, LLC License #: 33575  
 Address: P.O. Box 307 Wakeeney, Kansas 67672


Name of Party Responsible for Plugging Fees: Vincent Oil Corporation  
 State of Kansas County, Sedgwick, ss.

Richard A. Hiesch (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Richard A. Hiesch  
 (Address) 125 N. Market, Suite 1075 Wichita, Kansas 67202

SUBSCRIBED and SWORN TO before me this 22nd day of February, 2006

Yolanda Eubanks My Commission Expires: \_\_\_\_\_  
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**RECEIVED  
FEB 23 2009  
KCC WICHITA**

*Bm*