

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Gen-Dor Oil Company
Address: 8135 281st rd Cambridge, Kansas 67023
Phone: (620) 467 - 2615 Operator License #: 9576
Type of Well: oil well converted to ENHR Docket #: E-17807
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: October 26, 2005 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Mississippi Depth to Top: 2889 Bottom: 2900 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 035-23581-0001
Lease Name: Stolp
Well Number: 16
Spot Location (QQQQ): S/2 - S/2 - NE -
2310 ²⁹³⁹ Feet from North / South Section Line
1320 ¹⁵⁷⁶ Feet from East / West Section Line
Sec. 29 Twp. 30 S. R. 7 East West
County: Cowley
Date Well Completed: 6-13-1985 *original*
Plugging Commenced: 9-11-2005
Plugging Completed: 11-9-2005

KCC
BEM
2-27-06
RDM
Per GPS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	oil	335 ft	surface	8 5/8	335 ft	0 ft
		2940 ft	surface	4 1/2	2940 ft	1482 ft

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

9/11/05, graveled back to 50' above the perms @ 2839', dump bailed 6 sx cement on top of the gravel. 11/5/05, shot of 4 1/2 casing @ 1482', laid down casing and rigged up the pump top cement plug. 11/7/05, run and set 2 3/8 tubing @ 385', Gen-Dor oil Company mixed and pumped 138 sx 60/40 poz mix w/4% gel to surface. 11/8/05, tagged cement @ 198', run and set 2 2/8 tubing @ 195', Gen-Dor mixed and pumped 70 sx 60/40 poz mix w/4% gel to surface. 11/9/05 cement 6' from surface. Well is plugged and abandoned.

Name of Plugging Contractor: Gen-Dor Oil Company License #: 9576
Address: 8135 281st rd, Cambridge, Kansas 67023
Name of Party Responsible for Plugging Fees: Ron Whiteman dba Gen-Dor Oil Company
State of Kansas County, Cowley, ss.

I, Brent Whiteman (in joint venture with Ron Whiteman) (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Brent Whiteman

(Address) 3777 251st rd, Atlanta, Kansas 67008

ANN L. BRADY
Notary Public - State of Kansas
My Appt. Expires: 5-28-07

SUBSCRIBED and SWORN TO before me this 14 day of December, 2005
Ann L. Brady My Commission Expires: 5-28-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
FEB 22 2006

KCC WICHITA

673551

STOLP # 16

DATE 11-7-05 11-8-05

NAME Gen-Dor Oil Company		ORDER NO. 0001	
ADDRESS 8135 281st Rd		CITY, STATE, ZIP Cambridge, Kansas 67023	
SOLD BY	CASH	E.O.D.	CHARGE
			ON ACCT.
			MDSE. RETD. PAID OUT

QUAN.	DESCRIPTION	PRICE	AMOUNT
1	11-7, mixed + pumped		
2	138 sx 60/40 pos		
3	w/4% gel from		
4	385' to surface		
5			
6	11-8, mixed + pumped		
7	70 sx 60/40 pos		
8	w/4% gel from		
9	195' to surface		
10			
11	Pumped 208 sacks		
12	of 60/40 pos w/4%		
13	gel to fill to surface		
14			

RECEIVED BY Brent V. Altman	TAX	
	TOTAL	

adams 24705