

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

FEB 10 2006

KCC WICHITA

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil EOR Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/6/05 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

4165-69, 4132-36, 4119-25, Depth to Top: _____ Bottom: _____ T.D. _____

4070-73, 4022-26, 3985-92, Depth to Top: _____ Bottom: _____ T.D. _____

3968-74 Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-153-05190-00-01

Lease Name: Texaco Cahoj Unit

Well Number: #10

Spot Location (QQQQ): SE - NW - NE -
4290 Feet from North / South Section Line

1650 Feet from East / West Section Line

Sec. 9 Twp. 1 S. R. 34 East West

County: Rawlins

Date Well Completed: 11/7/59

Plugging Commenced: 1/26/06

Plugging Completed: 1/26/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	307	8 5/8	307	0
	Production	Surface	4203	5 1/2	4203	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Swift Services. Pumped 110 sxs SMD cmt & 400# hulls. Gained Circ w/25 bbls pumped. Pulled tbg to 1200'. Pumped 70 sxs SMD & 300# hulls & circ cmt to surface. TOH w/tbg. Hooked up to 8 5/8" csg. Pumped 25 sxs SMD & shut in @ 300#. Hooked up to 5 1/2". Pumped 30 sx SMD. Max press 600#. SI @ 0#. Let sit 30 mins. Casing full. Witnessed by Darrell Dipman w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.


State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



My Commission Expires: 11-4-07

Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten Signature]