

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED

FEB 16 2006

KCC WICHITA

Form CP-4  
December 2003

Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Woolsey Operating Company, LLC  
Address: 125 N. Market, Wichita, KS 67202  
Phone: (620) 886-8606 Operator License #: 33168  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 1/25/2006 (Date)  
by: Steve Pfeifer (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 2600 Bottom: 4244 T.D. 4301  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-007-20,761-00-01  
Lease Name: Gress  
Well Number: 1  
Spot Location (QQQQ): 20' N of N2-SW-SW *KCC SEM-06 2-17-06 RBDMS CP 2/3*  
1060 Feet from  North /  South Section Line  
660 Feet from  East /  West Section Line  
Sec. 28 Twp. 31 S. R. 12  East  West  
County: Barber  
Date Well Completed: spud 7/2/1979 original  
Plugging Commenced: 1/26/2006  
Plugging Completed: 1/30/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	335	None
				4 1/2	4329	2200


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1/26 - Set CIBP at 4160', spot 2 sacks cement with dump bailer, set CIBP at 2550', spot 2 sacks cement, stretch pipe, 1/27 - stretch and cut pipe at 2200', pull casing, 1/30 - run 2 3/8" tubing to 600', Allied load hole with 10 sacks gel, pump 50 sacks 60/40 POZ 6% gel pull tubing to 360', pump 50 sacks cement, pull to 40', load to surface

Name of Plugging Contractor: Clarke Corporation License #: 5105  
Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Woolsey Operating Company, LLC  
State of Kansas County, Barber, ss.

John Swinford (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford  
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 10 day of February, 20 06  
Glenda Morrison My Commission Expires: 11/30/06  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*DM*