

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 163-21,133 ⁵⁻ ~~00-00~~

LEASE NAME Schindler

WELL NUMBER #1

SPOT LOCATION C - SE-SE-SE

SEC. 18 TWP. 8 RGE. 17 ~~KEY (W)~~

COUNTY Rooks

Date Well Completed Nov. 20, 1988

Plugging Commenced 4-18-1985

Plugging Completed 4-18-1985

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR The Gene Brown Company

ADDRESS 407 S. Main, Plainville, Kansas 67663

PHONE # (913) 434-4811 OPERATORS LICENSE NO. 5635

Character of Well oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays - Dennis Hamel (verbal)

Is ACO-1 filed? yes If not, is well log attached? -0-

Producing formation Arb. - Lan/K.C. Depth to top 3148 bottom 3330 T.D. PBTD 3352

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	160	8 5/8"	160	none
Production		0	3369	4 1/2"	3369	40'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Attempted to pull pipe (4 1/2"). Casing parted 40' from surface. Pumped 400 sacks 60/40 pos. cement 8% gel with 8 sacks of hulls down the 8 5/8" and 4 1/2" casing. Maximum pressure was 400. Shut in. Pressure was 225#. Well plugged at 8:40 a.m. Cement stayed within 3' of surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services
 Address Hays, Kansas 67663

License No. 5287
 STATE CORPORATION COMMISSION
 RECEIVED
 MAY 13 1985
 MAY 13 1985


STATE OF Kansas COUNTY OF Rooks, ss.

Thomas E. Brown

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) X Thomas E. Brown

(Address) 407 S. Main - Plainville, Kans. 67663



SUBSCRIBED AND SWORN TO before me this 10th day of May, 1985

Kathy A. Wise
 Notary Public

My Commission expires: May 27, 1986