

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER <sup>15</sup> 163-21,507-00-00

LEASE NAME Maddy A

WELL NUMBER 1

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 18 TWP. 8 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed 1-15-82

Plugging Commenced 7-20-98

Plugging Completed 7-20-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Arroyo Petroleum

ADDRESS PO Box 12193 Wichita, Ks. 67227-2193

PHONE# (316) 721-7818 OPERATORS LICENSE NO. 03662

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-20-98 (date)

by Richard Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation L-KC, Arb. Depth to Top 3094' Bottom 3388' T.D. 3464'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	oil	3094	3336	8 5/8	248	0
Arb.	oil	3379	3388	4 1/2	3464	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Pf. thru tbg. 1700', 1345', 725'. Ran tbg. to 1700'. Allied pumped 100 sx 60/40 posmix 4% gel. Pull tbg. to 700'. Pump 40 sx 60/40 posmix 4% gel with 2 sx hulls. Pull tbg. Pump 25 sx down casing. Pressure casing to 400 #'s. Shut-in at 200 #'s. Pump 50 sx 60/40 posmix 4% gel with 1 sack hulls down 8 5/8". Pressure to 400 #'s and held. Complete at 3:00 P.M. 7-20-98

Name of Plugging Contractor Arroyo Petroleum License No. 03662

Address PO Box 12193 Wichita, Ks. 67227-2193

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Arroyo Petroleum

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Sharp

(Employee of Operator) or (Operator) or

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Gary Sharp

(Address) PO Box 122 Andover, Ks. 67002

SUBSCRIBED AND SWORN TO before me this 24 day of July, 19 98

Teresa U. Mendenhall  
Notary Public

My Commission Expires: 1/19/2000

TERESA U. MENDENHALL  
Notary Public - State of Kansas  
My Appt. Expires 1/19/2000

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 24 1998  
JUL 24 1998  
CONSERVATION DIVISION  
WICHITA, KS