


15-163-00589-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Rooks County. Sec. 18 Twp. 8 Rge. 17 (E) W. (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
Lease Owner Sidey Oil Company
Lease Name V. D. Sidey Oil Company-Reeder Well No. 1
Office Address Russell, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced August 29 19 52
Plugging completed September 1 19 52
Reason for abandonment of well or producing formation _____
Dry hole
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3376 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3376 feet to surface feet for each plug set.

Hole had been plugged back to 3055 and cement plug installed; hole filled with mud from 3055 to 200 feet; rock bridge installed between 200 feet and 190 feet; fifteen sacks of cement dumped in hole to form cement plug and hole bailed clear; twenty additional sacks of cement placed in hole with dump bailer, forming a cement plug from 200 feet to 78 feet; mud placed in hole to 35 feet; rock bridge installed from 35 to 30 feet; Ten sacks of cement poured in hole forming cement plug to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes and Sons Pipe Fubling Company
Address Russell, Kansas.

STATE OF Kansas, COUNTY OF Russell, ss.
V. D. Sidey (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
(Address) _____

SUBSCRIBED AND SWORN TO before me this 13th day of September, 1952
Lorita D. Embury Notary Public.

My commission expires April 4, 1956

23-8390-s 6-51-20M

PLUGGING
FILE SEC 18 T 8 R 17 W
BOOK PAGE 42 LINE 19

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1952
SEP 17 1952
CONSERVATION DIVISION
Wichita, Kansas

SIDEY DRILLING COMPANY

BUILDING & LOAN BLDG.

P. O. BOX 387

RUSSELL, KANSAS

COMPANY V. D. SIDEY OIL COMPANY

SEC. 18 T. 8 R. 17

FARM REEDER NO. 1

LOC. S $\frac{1}{2}$ SE

TOTAL DEPTH 3376
COMM. 5-10-52 COMP. 5-20-52
SHOT OR TREATED
CONTRACTOR V. D. SIDEY DRILLING COMPANY
ISSUED

COUNTY ROCKS

CASING
20 10
15 $\frac{1}{2}$ 8 $\frac{1}{4}$ --- 105'
12 $\frac{1}{2}$ 6"
18% 5 5/16 --- 3140'

ELEVATION 1929 DF
1927 GR
PRODUCTION DRY HOLE

FIGURES INDICATE BOTTOM OF FORMATIONS

0-30	Shale	2515-2610	Lime & Shale
30-40	Sand	2610-2690	Lime & Shale
40-105	Shale	2690-2740	Lime
105-280	Gray Shale	2740-2760	Shale & Lime
280-335	Gray Shale	2760-2850	Shale & Lime
335-365	Shale & Shells	2850-2900	Lime & Shale
365-400	Shale	2900-2970	Lime & Shale
400-490	Shale & Shells	2970-2985	Lime & Shale
490-635	Shale	2985-3020	Lime & Shale
635-660	Sand	3020-3030	Lime
660-680	Shale	3030-3085	Lime & Shale
680-695	Sand	3085-3135	Lime & Shale
695-760	Shale	3135-3175	Lime
760-790	Sand	3175-3215	Lime
790-815	Shale	3215-3260	Lime
815-995	Sand	3260-3291	Lime
995-1030	Red Bed	3291-3340	Lime
1030-1285	Red Bed & Shells	3340-3376	Lime T. D.
1285-1326	Anhydrite		
1326-1340	Shale & Shells		
1340-1605	Shale & Shale		
1605-1775	Shale & Shells		
1775-1850	Shale & Shells		
1850-1920	Lime & Shale		
1920-2000	Broken Lime		
2000-2050	Broken Lime		
2050-2060	Lime & Shale		
2060-2165	Lime & Shale		
2165-2240	Lime		
2240-2340	Lime & Shale		
2340-2425	Lime & Shale		
2425-2515	Lime & Shale		

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

I, V. D. Sidey, of the Sidey Drilling Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Reeder #1 Well.

NOTARY PUBLIC

SEP 17 1952
SEP 17 1952
CONSERVATION DIVISION V. D. Sidey
Wichita, Kansas

Subscribed and sworn to before me this 13th day of September, 1952.

My Commission Expires: April 4, 1956

Louisa D. Embury
Notary Public

PLUGGING
FILE SEC. 18 T. 8 R. 17
BOOK PAGE 42 LINE 11