

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Heartland Oil & Gas Corporation  
Address: 1610 Industrial Park Drive Paola KS 66071  
Phone: (913) 294-1400 Operator License #: 33233  
Type of Well: Gas Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)*  
The plugging proposal was approved on: 12-07-05 (Date)  
by: Taylor Herman (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 2290  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 085-20064-00-00  
Lease Name: Brock  
Well Number: 34 - 19  
Spot Location (QQQQ): \_\_\_\_\_ - C - SW - SE  
655 Feet from  North /  South Section Line  
2115 Feet from  East /  West Section Line  
Sec. 19 Twp. 6 S. R. 16  East  West  
County: Jackson  
Date Well Completed: 1-09-04  
Plugging Commenced: 2-02-06  
Plugging Completed: 2-03-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	GL	217'	8 5/8	217'	None
	Production	GL	2274'	5 1/2	2274'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing and tagged at 2219' with tubing at 2215', pumped 11.25 bbls of Gelled water and pulled tubing to 2115'. Pumped 39.0 bbls of Gelled water and pumped 25 sx of Class A cement with 1 sx of cottonseed hulls. Displaced with 7.5 bbls of gelled water. Had gel from 2114' to 2215' and cement from 1897' to 2115' with Gelled water from 250' to 1897'. On 2-03-06, pulled tubing to 251' and circulated cement to surface with 30 sx of Class A cement. Pulled tubing and capped well in.

Name of Plugging Contractor: Hurricane Well Service, Inc. License #: 32006  
Address: PO Box 782228 Wichita KS 67278-2228  
Name of Party Responsible for Plugging Fees: Hurricane Well Service, Inc.  
State of Kansas County, Sedgwick, ss. \_\_\_\_\_  
Darrel G. Walters (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

**RECEIVED**  
**KANSAS CORPORATION COMMISSION**  
**MAR 02 2006**  
**CONSERVATION DIVISION**  
**WICHITA, KS**

(Signature) [Signature]  
(Address) PO Box 782228 Wichita KS 67278-2228

SUBSCRIBED and SWORN TO before me this 2 day of March, 2006



Terri Buehler My Commission Expires: 7-21-08  
Notary Public

*Tam*