

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

FEB 22 2006

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Lease Operator: Hutchinson Oil Company
Address: P.O. Box 521 Derby, Ks. 67037
Phone: (316) 788 - 5440 Operator License #: 5614
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 185-23,0830000
Lease Name: Sleeper "J"
Well Number: 1-21
Spot Location (OQQQ): 75'E. NW NW SW
2336 Feet from _____ North / South Section Line
425 Feet from East / West Section Line
Sec. 21 Twp 22 S. R. 11 East West
County: Stafford
Date Well Completed: _____
Plugging Commenced: 2-6-06
Plugging Completed: 2-8-06

KCC
3-1-06
Per Oper
Steve
PKT

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	266'	None
				4-1/2"	2892'	1502'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 2370' and 4 sacks cement. Cut casing loose @1502', pulled up to 600', pumped 10 sacks gel and 50 sacks cement, pulled up to 300', pumped 50 sacks cement, pulled up to 40' and topped off with 20 sacks cement, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524


Name of Party Responsible for Plugging Fees: Hutchinson Oil Company
State of Kansas County Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 17th day of February, 2006

Irene Herzberg Notary Public My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT