

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Taurus Oil Company  
Address: P O Box 981 Hays, Ks. 67601  
Phone: (785) 628-1727 Operator License #: 6127  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: January 20, 2006 (Date)  
by: Roger Moses (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3776 Bottom: 3830 T.D. 3830  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 051-23731-00-00  
Lease Name: Wilson B  
Well Number: 3  
Spot Location (QQQQ): \_\_\_\_\_ - NW - NW - NE  
4950 Feet from  North /  South Section Line  
2310 Feet from  East /  West Section Line  
Sec. 29 Twp. 14 S. R. 19  East  West  
County: Ellis  
Date Well Completed: March 22, 1984  
Plugging Commenced: February 1, 2006  
Plugging Completed: February 1, 2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Oil and Water	3776	3830	5 1/2	3829	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

8 5/8' SP @ 258' w/150 sxs. 5 1/2" csg @3829' w/625 sxs.

Plugging procedure; squeezed 155 sxs cement, 20 sxs gel and 400 lbs hulls down 5 1/2" casing to 1000 # maximum, 650# shut-in.

Annulus was pressured to 500#, would not take cement. Plug down. Cement type, 60/40 poz mix with 10% gel.

Name of Plugging Contractor: Allied Cementing Company, Inc. License #: 99996

Address: P O Box 31, Russell, Kansas 67665

Name of Party Responsible for Plugging Fees: Jeff Koron


State of Kansas County, Ellis, ss.

JEFF KORON (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) PO BOX 31 HAYS 67601

SUBSCRIBED and SWORN TO before me this 24 day of FEB, 20 06



Trudi McFarren My Commission Expires: 3/26/09  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*Rec'd 02-27-06*