

RECEIVED

MAR 01 2006

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

KCC WICHITA

Lease Operator: Hartman Oil Co., Inc.

Address: 12950 E 13th St. N - Wichita, Ks. 67230-1457

Phone: (620) 277-2511 Operator License #: 30535

Type of Well: oil well - not active - when purchased Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2/15/06 (Date)

by: Richard Lacey W/ KCC - Witness by Ken Jehliik (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
(MISS OH) Depth to Top: 4610' Bottom: 4707' T.D. 4707'
MARMANTON Depth to Top: 4282' Bottom: 4298' T.D. 4298'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-055-10158-00-00

Lease Name: NUNN

Well Number: #3

Spot Location (QQQQ): _____ - SE - SW - NE
990 2310 Feet from North / South Section Line

990 1650 Feet from East / West Section Line

Sec. 27 Twp. 21 S. R. 34 East West

County: Finney

Date Well Completed: 12/9/47 Drilled

Plugging Commenced: 2/15/06

Plugging Completed: 2/21/06

KCC
BEM
3-3-06
RBDMS
CP 2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		286'	surface	10-3/4"	286'	none
		4610'	SURFACE	5-1/2"	4610'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

(2/15/06) set CIBP @ 2316' - set 2nd CIBP @ 1200' - perforate 5-1/2" csg @ 1100' 2/spf - (2/21/06) Ran 1100' 2-7/8" tbg - spot 100 sks class A common w/ 3% CC w/ 100# hulls mixed in after mixing 60 sks - Note: Full returns while spotting cmt. then well went on vacuum - shut-in 5-1/2" csg 2/hrs - tag cmt. @ 297' - filled 5-1/2" csg to surface w/ 35 sks 60-40 poz w/ 6% gel (stayed full) Hooked up to 5-1/2" x 10-3/4" annulus - pumped 265 sks 60-40 poz w/ 6% gel down 10-3/4" @ 200# psi - closed in annulus- holding @ 100# psi

Name of Plugging Contractor: Allied cement Co. & Hartman Oil Co., Inc. License #: 30535

Address: 12950 E 13th St N - Wichita, Ks. 67230-1457

Name of Party Responsible for Plugging Fees: Hartman Oil Co., Inc.

State of Kansas County, Finney, ss.

S T Mitchell (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) S.T. Mitchell

(Address) 4550 W 9 Mi Rd Garden City, KS 67846

SUBSCRIBED and SWORN TO before me this 27th day of February, 2006

Mary L Riffel My Commission Expires: 3/1/13/2010
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202
MARY L. RIFFEL
MY COMMISSION EXPIRES

[Handwritten initials]

DATE 2/21/2006

TIME 4:00 AM/PM

OPERATOR Hartman Oil Co

OPERATOR LICENSE NO. 30535 API# 15- _____

PLUGGING CONT. Allied Cementing LICENSE NO. _____

PUSHER Max WITH Allied

RECEIVED

MAR 01 2006

KCC WICHITA

LEASE NAME & WELL NO. Nuan #3

LEGAL SE SW 1/4 Sec 27-21^s-34^w COUNTY Finney

GPS: Latitude 38.20043 Longitude 101.03609

TD 4707 PBSD 4310 C.P. — S.P. 10^{3/4}% 286' w/400sx

OTHER CASING 5 1/2 % 4610' WI 300 sx SX CMT _____

PERFORATED AT Miss OH 4610-4707, Marmaton 4282-4288 (CIBP % 4310), Tbg stuck in hole @ 3251. Unable to get below 2460 w/ 3 7/8 bit

LINER FROM None TO _____ WI _____ SX CMT _____

MARKER DEPTH Stone Coral @ 2090', Permian Top @ 1100'

BOTTOM PLUG CIBP % 2305 w/ 2sx cmt
CIBP % 1200' w/ 2sx cmt

CASING RECOVERY None

TOP PLUG(S) Perforate 2 holes @ 1100'. Run 2 7/8 tbg to 1100'
(21665)
Spot 100 sx CIA + 3% CC w/ 100 # balls mixed in after mixing 60sx.

Full circulation while spotting cmt, then well went on vacuum.
Wait 2 hrs. Tag Top in 5 1/2" csg w/ sinker bars @ 297' ss. Top of fluid in 5 1/2" csg = 225'. 7 bbl cmt went out perms @ 1100'. (363x)

Fill 5 1/2" csg from the top with 35 sx 60/40 Poz 6% gel. Stayed full
Hook up to 5 1/2 x 10 3/4 annulus & pump 265 sx 60/40 Poz 6% gel.
Pressure increased to 200 #, holding 100 #, close annulus in

STARTING TIME 10:00 AM COMPLETION TIME 4:00 PM

TYPE OF CEMENT & CEMENTER CIA + 3% CC and 60/40 Poz 6% gel

PLUGGED THROUGH: CASING TUBING DRILL PIPE (CIRCLE ONE)

TECHNICIAN WHO GAVE PLUGGING ORDERS Richard Lacey

TECHNICIAN WHO WITNESSED PLUG Ken Sehlitz

ALLIED CEMENTING CO., INC.

22379

Federal Tax I.D.# ~~45-11111~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Oakley

DATE	2-21-06	SEC	27	TWP	21s	RANGE	34w	CALLED OUT		ON LOCATION	10:45 AM	JOB START	11:00 AM	JOB FINISH	3:15 PM	
LEASE	Nunn	WELL #	3	LOCATION	834 Gano Rd 8w 1/2 N w/s				COUNTY	Firmey	STATE	KS				
<input checked="" type="radio"/> OLD OR NEW (Circle one)																

CONTRACTOR Plains Well Service
 TYPE OF JOB Plug old Hole
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2 DEPTH _____
 TUBING SIZE 2 1/8 DEPTH 1101'
 DRILL PIPE _____ DEPTH _____
 TOOL Cast Iron B Plug DEPTH 1200' + 2305
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. 1100'
 DISPLACEMENT _____

OWNER Same
 CEMENT
 AMOUNT ORDERED 100 sks Com 390 cc
300 sks 60/40 P02 690 Gel
100^g Hulls
 COMMON _____ @ _____
 POZMIX _____ @ _____
 GEL _____ @ _____
 CHLORIDE _____ @ _____
 ASC _____ @ _____
 _____ @ _____
Hulls 1sk @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 HANDLING _____ @ _____
 MILEAGE _____ @ _____

EQUIPMENT
 PUMP TRUCK CEMENTER Dean
 # 373-281 HELPER Andrew / Max
 BULK TRUCK
 # 377 DRIVER Kelley
 BULK TRUCK
 # 394 DRIVER ALGN

REMARKS:
pump Had Bkw. mix 60sk Then mix 200^g
Hulls in cement. Disp 1 Gbl. waited 2hrs
Tag Cement at 297'. Tag csg off
w/ 35 sks. Pump 265 sks 60/40 690 Gel
down B Side Max Pressure 200^g
Thank you

CHARGE TO: Hartman Oil
 STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Harold D Wright
A. J. [unclear]
2/23/06

TOTAL _____
 SERVICE
 DEPTH OF JOB _____
 PUMP TRUCK CHARGE _____
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 75 miles @ _____
 MANIFOLD _____ @ _____
 _____ @ _____
 _____ @ _____

TOTAL _____
 PLUG & FLOAT EQUIPMENT
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 TOTAL _____

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____

RECEIVED
 MAR 01 2006
 KCC WICHITA