

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

Lease Operator: Anadarko Petroleum Corporation

Address: 1201 Lake Robbins Dr, The Woodlands, TX 77380

Phone: (832) 636-8380 Operator License # 4549

Type of Well: Oil Docket # (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: Ken Jehlik (KCC District Agent's)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Wildcat Depth to Top: 6692 Bottom: 6708 T.D. 6820

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number 15- 189-22429 - 00 -00

Lease Name HJV Mahoney A

Well Number 1

Spot Location (QQQQ) W/2 E/2 SE SW

685 Feet from North South Line of Section

2100 Feet from East West Line of Section

Sec. 2 Twp. 34 S. R. 37 East West

County: Stevens

Date Well Completed: 01/28/2003

Plugging Commenced: 01/18/2006

Plugging Completed: 01/19/2006

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out). Includes handwritten notes like 'KCC 3-7-06 3-1/2" PLT per 250ms'.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Set 20 sxs cement to plug perfs @ 6692'-6532'. Shot 5-1/2" casing loose @ 2016'. Pull to 1830 - circulate hole with mude & mix 50 sxs cement - plug 1830' to 1680' - pull to 6--' - mix 40 sxs cement plug 600' to 480'. Pull to 40' - mix 10 sxs cement 40' to surface. Cut & Cap 8-5/8" casing 3' below GL.

Name of Plugging Contractor: Sargent & Horton Plugging, Inc. License # 31151


Address Route 1, Box 49BA, Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Martha C. Howard (Employee of Operator) or (Operator) above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.



(Signature) Martha C. Howard

(Address) 1201 Lake Robbins Dr., The Woodlands, TX 77380

SUBSCRIBED and SWORN TO before me this 28th day of February, 2006

Bertha Neff Notary Public My Commission Expires: 12-27-09