

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-04391-00-00
Spot: SWNE Sec/Twnshp/Rge: 36-20S-6W
3300 feet from S Section Line, 2310 feet from E Section Line
Lease Name: CARLSON G W Well #: 3
County: RICE Total Vertical Depth: 3348 feet

Operator License No.: 33005
Op Name: RANDON PRODUCTION COMPANY LL
Address: 2761 REMINGTON RD
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	3300		
SURF	10	161		

\$108⁸¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/18/2006 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/18/2006 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded to 3250' and capped with 6 sacks of cement. Perforated at 800', 400', and 250'. Ran tubing to 800' and pumped 50 sacks of cement at 350 lbs. Pulled tubing to 400' and pumped 50 sacks of cement at 450 lbs. Pulled tubing to 250' and circulated cement to surface at 500 lbs.

60/40 posmix with 4% gel

Copeland #C030134
Log Tech #4389

**RECEIVED
KCC DISTRICT #2
FEB - 3 2006
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE 2-28-06

INV. NO. 2006061203 *A*

RECEIVED

FEB 27 2006

KCC WICHITA