

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-05176-00-00  
Spot: SWNE Sec/Twnshp/Rge: 36-20S-6W  
3300 feet from S Section Line, 2640 feet from E Section Line  
Lease Name: CARLSON G W Well #: 2  
County: RICE Total Vertical Depth: 3346 feet

Operator License No.: 33005  
Op Name: RANDON PRODUCTION COMPANY LL  
Address: 2761 REMINGTON RD  
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6	3286		
SURF	10	137		

#108<sup>75</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/18/2006 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/18/2006 5:20 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded to 3250' and capped with 6 sacks of cement. Perforated at 800', 400', and 250'. Ran tubing to 800' and pumped 50 sacks of cement. Pulled tubing to 400' and pumped 50 sacks of cement. Pulled tubing to 250' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland #C0303135  
Log Tech #4390

RECEIVED  
KCC DISTRICT #2  
FEB - 3 2006  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 2-28-06  
INV. NO. 2006061203

ra

RECEIVED  
FEB 27 2006  
KCC WICHITA