

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-19301-00-05

Spot: SENE

Sec/Twnshp/Rge: 34-21S-19E

4261 feet from S Section Line,

286 feet from E Section Line

Lease Name: NORTH WELDA

Well #: 65

County: ANDERSON

Total Vertical Depth: 958 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPE

Address: 4700 HIGHWAY 56

OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

COND	10	10		
------	----	----	--	--

PROD	4.5	955		
------	-----	-----	--	--

SURF	7	897		
------	---	-----	--	--

135 SX CMT

CIRCULATED TO SURFACE

35⁰⁰

Well Type: GS

UIC Docket No:

Date/Time to Plug: 11/07/2005 8:00 AM

Plug Co. License No.: 6372

Plug Co. Name: SPLANE PULLING & ROUST SVS, INC.

Proposal Rcvd. from: BERNIE ROCKERS

Company:

Phone: (785) 448-4816

Proposed
Plugging
Method:

SET RETAINER @ 845' AND PLUGGED WITH 55 SX CMT. CLASS A CMT. WILL PERFORATE TEST AND PLUG PER KCC UNDERGROUND POROSITY GAS STORAGE REQUESTS TESTING ALTAMONT, IOLA AND DENNIS LS. RETAINER WILL BE SSET BETWEEN EACH SET OF PERFORATIONS SQUEEZED AND PRESSURED BACK. PLUG SOLID TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 11/07/2005 5:00 PM

KCC Agent: TOM WELSH

Actual Plugging Report:

ON 02-08-05 CEMENT RETAINER SET @846' PUMP 55 SX CEMENT ON 11-07-05 PERFORATED 628-638 & 612-622' (2 SHOT PER FOOT) NO GAS RAN 2 3/8" PIPE TO 839' PUMP 20 SX CEMENT PULL UP TO 640' & WASH SET RETAINER 590' PIPE STUCK IN RETAINER PUMP 40 SX PSI 600 LBS STACKED 15 SX ON TOP OF RETAINER & WASH TO 450' PERF 416-426' NO GAS PERF 254-260' NO GAS RAN TUBING 450' PUMP CEMENT TO SURFACE PULL TUBING TOP OFF WELL AND SQUEEZED PSI 1000 LBS

RECEIVED
KCC DISTRICT #3

FEB 14 2006

CHANUTE, KS

TJw

Perfs:

Top	Bot	Thru	Comments
908	952		

Remarks:

Plugged through: TBG

District: 03

Signed

Thomas J. Welch

(TECHNICIAN)

INVOICED

DATE 2-28-06

INV. NO. 2006061206

RECEIVED

FEB 27 2006

KCC WICHITA