

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-29321-00-00  
Spot: SENE SW Sec/Twnshp/Rge: 22-26S-18E  
1700 feet from S Section Line, 3090 feet from E Section Line  
Lease Name: CANNON A Well #: 44  
County: ALLEN Total Vertical Depth: 865 feet

Operator License No.: 5488  
Op Name: TWM PRODUCTION CO., A GENERAL P  
Address: 1150 HWY 39  
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	21		

# 35<sup>00</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/11/2006 10:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY  
Proposal Rcvd. from: MIKE WIMSETT Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 865'. THE PLUGGING PROPOSAL WAS TO PLACE AT LEAST A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 500', AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE  
Date/Time Plugging Completed: 02/11/2006 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

TUBING WAS RAN INTO THE WELL TO 875'. 75 SACKS OF CEMENT WERE PUMPED THROUGH THE TUBING TO 865'. FILLUP SHOULD HAVE BEEN TO ABOVE 500'. THE TUBING WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED  
KCC DISTRICT #3

FEB 22 2006 CPT

CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED

FEB 27 2006

KCC WICHITA

INVOICED

DATE

2-28-06

INV. NO.

2006061208