

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22296-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 2-21S-7W
1140 feet from S Section Line, 1170 feet from E Section Line
Lease Name: JOHNSON Well #: 7
County: RICE Total Vertical Depth: 3514 feet

Operator License No.: 32755
Op Name: MA & MC OIL & GAS LLC
Address: 602 S. CLARK
LYONS, KS 67554

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3514		100 SX CMT
SURF	8.625	211		175 SX CMT

114²¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/16/2006 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 01/16/2006 10:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3375' and capped with 5 sacks of cement. Cut off casing at 2640'.
Pulled casing to 1050' and pumped 35 sacks of cement with 100 lbs of cotton seed hulls. Pulled casing to 600' and pumped 35 sacks of cement with 100 lbs of cotton seed hulls. Pulled casing to 265' and circulated cement to surface with 100 lbs of cotton seed hulls.

60/40 posmix with 4% gel

United Cement #6751

Perfs:

Top	Bot	Thru	Comments
3479	3481		
3468	3472		
3452	3458		
3424	3434		

RECEIVED
KCC DISTRICT #2
FEB - 3 2006
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED
DATE 2.28.06
INV NO 2006061197

RECEIVED
FEB 27 2006
KCC WICHITA