

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20257-00-00
Spot: E2NESE Sec/Twnshp/Rge: 35-22S-2W
2098 feet from S Section Line, 380 feet from E Section Line
Lease Name: STUCKY Well #: 1
County: HARVEY Total Vertical Depth: 2978 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2750		
PROD	4.5	2978	1000	115 SX CMT
SURF	8.625	223	0	175 SX CMT

96 79

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2005 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE, INC. Phone: (620) 463-5161

Proposed Plugging Method: Sand to 2615' w/ 4 sxs cmt. Perfs 2665' - 2670'. Shoot casing and pull to 0'. Run polyline to 450' w/ 35 sxs. Pull polyline to 275' and circ cmt to surf.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE
Date/Time Plugging Completed: 07/18/2005 11:00 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2615' and topped with 4 sacks of cement. Shot 4-1/2" casing at 1000' and pulled the same. Ran polyline to 450' and circulated 170 sacks of cement to surface.

60/40 posmix with 4% gel

Copeland #25816

Perfs:

Top	Bot	Thru	Comments
2665	2670		

**RECEIVED
KCC DISTRICT #2
FEB 14 2006
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed

Michael Wilson

(TECHNICIAN)

INVOICED

DATE 2-28-06

INV. NO. 2006061188

M

RECEIVED

FEB 27 2006

KCC WICHITA