

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20979-00-00  
Spot: W2SWNE Sec/Twnshp/Rge: 36-19S-10W  
3373 feet from S Section Line, 2438 feet from E Section Line  
Lease Name: LINK Well #: 1  
County: RICE Total Vertical Depth: 3361 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

| String | Size  | Depth (ft) | Pulled (ft) | Comment    |
|--------|-------|------------|-------------|------------|
| PROD   | 5.5   | 3359       |             | 100 SX CMT |
| SURF   | 8.625 | 250        |             | 175 SX CMT |

# 109<sup>23</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/30/2006 11:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: KEVIN WILES Company: AMERICAN WARRIOR Phone: (620) 272-4996

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/30/2006 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU. Perforated at 1225', 850', and 300'. Ran tubing to 3150' and pumped 50 sacks of cement. Pulled tubing to 1225' and pumped 35 sacks of cement. Pulled tubing to 850' and pumped 35 sacks of cement. Pulled tubing to 300' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland Cement #C030206  
Log Tech #16730

Perfs:

| Top                                                        | Bot  | Thru | Comments |
|------------------------------------------------------------|------|------|----------|
| 3359                                                       | 3361 |      |          |
| RECEIVED<br>KCC DISTRICT #2<br>FEB - 3 2006<br>WICHITA, KS |      |      |          |

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 2-28-06  
INV NO 2006061187

RECEIVED  
FEB 27 2006  
KCC WICHITA