

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22254-00-02
Spot: NWNESW Sec/Twnshp/Rge: 2-18S-7W
2310 feet from S Section Line, 1550 feet from W Section Line
Lease Name: JANSSEN A Well #: 4
County: RICE Total Vertical Depth: 3350 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3316	2035	115 SX CMT
SURF	8.625	219	0	130 SX CMT

\$ 108⁸⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/25/2006 1:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ WitnessType: PARTIAL
Date/Time Plugging Completed: 01/25/2006 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2700' and capped with 4 sacks of cement. Cut off casing at 2090'.
Pulled casing to 900' and pumped 35 sacks of cement. Pulled casing to 600' and pumped 35
sacks of cement. Pulled casing to 270' and circulated cement to surface.

60/40 posmix with 4% gel
Copeland Cement #C030145

Perfs:

Top	Bot	Thru	Comments
2834	2838		
2750	2900		

RECEIVED
KCC DISTRICT #2
FEB - 3 2006
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 2-28-06
INV. NO. 2006061192

RECEIVED
FEB 27 2006
KCC WICHITA