

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22424-00-00  
Spot: NWNE Sec/Twnshp/Rge: 14-18S-7W  
4950 feet from S Section Line, 990 feet from E Section Line  
Lease Name: BEHNKE C Well #: 3  
County: RICE Total Vertical Depth: 3300 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W. 93 N.  
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3298	2080	150 SX CMT
SURF	8.625	218	0	150 SX CMT
T1	2.375	3245		

#107<sup>25</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/24/2006 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ WitnessType: NONE  
Date/Time Plugging Completed: 01/24/2006 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3145' and put 4 sacks of cement on top. Cut off casing at 2013'. Pulled casing to 900' and pumped 35 sacks of cement. Pulled casing to 600' and pumped 35 sacks of cement. Pulled casing to 270' and circulated cement to surface.

60/40 posmix with 4% gel

Copland Cement #C030202

Perfs:

Top	Bot	Thru	Comments
3210	3216		
3196	3204		

RECEIVED  
KCC DISTRICT #2  
FEB - 3 2006  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)  
RECEIVED

FEB 27 2006

KCC WICHITA

Form CP-2/3

INVOICED

DATE 2-28-06

INV. NO. 2006061192