

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20980-00-00

Spot: W2SESE

Sec/Twnshp/Rge: 13-19S-10W

297 feet from S Section Line, 741 feet from E Section Line

Lease Name: LINK LEWIS

Well #: 3

County: RICE

Total Vertical Depth: 3273 feet

Operator License No.: 4058

Op Name: AMERICAN WARRIOR, INC.

Address: PO BOX 399

GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3270		
SURF	8.625	250		

106 37

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/31/2006 10:30 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: KEVIN WILES

Company: AMERICAN WARRIOR, INC.

Phone: (620) 275-7461

Proposed
Plugging
Method:

See actual report.

Plugging Proposal Received By: MICHAEL WILSON

WitnessType: PARTIAL

Date/Time Plugging Completed: 01/31/2006 12:45 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU. Perforated at 1225', 850', and 300'. Ran tubing to 3250' and pumped 50 sacks of cement. Pulled tubing to 1225' and pumped 35 sacks of cement. Pulled tubing to 850' and pumped 35 sacks of cement. Pulled tubing to 300' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland #C030209

Log Tech #16732

**RECEIVED
KCC DISTRICT #2
FEB - 3 2006
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 2-28-06

INV. NO. 2006061187

RECEIVED

FEB 27 2006

KCC WICHITA