

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20689-00-02
Spot: NWNW Sec/Twnshp/Rge: 24-29S-41W
1200 feet from N Section Line, 660 feet from W Section Line
Lease Name: UNEY Well #: 24-1
County: STANTON Total Vertical Depth: 5744 feet

Operator License No.: 33002
Op Name: WESTPORT OIL AND GAS COMPANY L
Address: 5735 PINELAND, SUITE 300
DALLAS, TX 75231

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5310		
CIBP		5490		
COND	20	40		WITH 4 YDS CMT
PROD	5.5	5596	850	WITH 1200 SX CMT
SURF	8.625	1653		WITH 550 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/14/2006 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS WITH 50 SX CMT. PLUG AT 1700' WITH 25 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/14/2006 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 500# HULLS WITH 50 SX CMT. 1ST PLUG AT 1700' WITH 25 SX CMT INSIDE 5 1/2" CASING. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.


Perfs:

Top	Bot	Thru	Comments
5496	5500		
5340	5468		
4746	4858		
4666	4686		
4507	4588		

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed

Jim Holland (TECHNICIAN)

RECEIVED

FEB 23 2006

KCC WICHITA

INVOICED

DATE 2-24-06
IN. NO. 2006061182