

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24455-00-00
Spot: SWNESW Sec/Twnshp/Rge: 14-16S-21W
1650 feet from S Section Line, 1650 feet from W Section Line
Lease Name: SUNLEY Well #: 1-14
County: NESS Total Vertical Depth: 4188 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	261		WITH 175 SX CMT

#136¹¹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/19/2006 11:00 PM
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.
Proposal Rcvd. from: CAROL NICHOLS Company: MALLARD, J. V., INC. Phone: (620) 241-4640

Proposed Plugging Method: 1ST PLUG AT 1590' WITH 50 SX CMT. 2ND PLUG AT 990' WITH 80 SX CMT. 3RD PLUG AT 510' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 02/20/2006 12:45 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG AT 1590' WITH 50 SX CMT. 2ND PLUG AT 990' WITH 80 SX CMT. 3RD PLUG AT 510' WITH 40 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.


Perfs:

Remarks: USED 60/40 POZMIC 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

INVOICED
DATE 2-23-06
REF. NO. 2006061171

District: 01



Signed

Jerry W. Stapleton PRT/JT
(TECHNICIAN)

RECEIVED
FEB 23 2006
KCC WICHITA

Form C2-27