

3 022994

15-001-02059-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001--047

SE,NW,NE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.

4231 feet from south section line

1918 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101 100Operator: STATE OF KANSAS Fee Fund

Name & _____

Address _____

AB oil well X Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLCLic. # 30670Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 2:00P.M. Day: _____ 2 Month: 12 2006Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY900' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THEPLUGGING PROPOSAL WAS TO CIRCULATE THE 2" CASING FULLOF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITELPlugging attended by Agent: All X Part _____

TECHNICIAN

None _____

Operations Completed: Hour: 5:00P. Day: _____ 2 Month: 1 2006Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 905'.CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROMTHE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENTWAS FILLED FROM SURFACE. 51 SACKS OF CEMENT WERE PUMPED INTOTHIS WELL.Remarks: (GPS SESSION PT. NO.12.) (NO OTHER WELL NO. IS AVAILABLE.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANRECEIVED
01-19-06
JAN 19 2006
KCC WICHITA