

3 022999

15-001-02061-00-0

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001--050

NW,SW,NE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.

3734 feet from south section line

2067 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101-400Operator: STATE OF KANSAS

Name & _____

Address _____

AB oil well X Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLCLic. # 30670Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 9:00A.M. Day: 17 Month: 1 2006Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: VISIBLE AT SURFACE ON THIS WELL WAS 6" CASING ONLY. THECASING WAS PROBABLY CEMENTED IN AT T.D. ONLY. THE PLUGGINGPROPOSAL WAS TO PERFORATE THE CASING SEVERAL TIMES AND TOCIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

RECEIVED

JAN 30 2006

KCC WICHITA

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN
None XOperations Completed: Hour: 11:00A.M. Day: 17 Month: 1 2006Actual Plugging Report: THE 6" CASING WAS PERFORATED AT 335' ANDWAS PERFORATED AT 200'. 1" PIPE WAS WASHED INTO THE WELL TO 475'.CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROMTHE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WASFILLED FROM SURFACE. 130 SACKS OF CEMENT WERE PUMPED INTO THISWELL.Remarks: (GPS SESSION PT. NO.15.) (NO OTHER NUMBER IS AVAILABLE FOR THIS WELL.)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

Bum