

3 022989

15-001-28056-0004

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

KCC
BEM
3-3-06
PDR/Na

API NUMBER CONTROL NO. 20060001--038
NE,NW,NE 1/4 Sec/Twp/Rge S.24-T.26S.-R.17E.
5154 feet from south section line
1679 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101-400
Operator: STATE OF KANSAS
Name & _____
Address _____
AB oil well _____ Gas Well _____ SWD Well/ Input Well _____

Lease/Well# JONES NO.19
County ALLEN
Well Total Depth 927" feet
Production Pipe: 2 7/8" Size Feet 927'
Surface Casing: 7" Size Feet 20'
E-25,284 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: _____ Day: 27 Month: 12 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 927" THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part _____
TECHNICIAN None _____

Operations Completed: Hour: _____ Day: 27 Month: 12 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 800P.S.I.. 28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.1.) (WELL NO.19. API NO. 15-001-28,506-00-01.)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
01-19-06
JAN 19 2006
KCC WICHITA

BEM