

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20728-00-00
Spot: SENENE Sec/Twnshp/Rge: 22-31S-9W
990 feet from N Section Line, 330 feet from E Section Line
Lease Name: GREEN Well #: 4
County: HARPER Total Vertical Depth: 4490 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N. MARKET, STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4490		220 SX CMT
SURF	8.625	312		270 SX CMT

\$ 145,93

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/13/2006 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Perfs 4436' - 4444'; PBTd 4488'; Sand back to 4370' with 4 sxs cmt; 35 sxs @ 1475'; 35 sxs @ 1000'; and circ 360' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 02/13/2006 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were sanded back to 4370' and capped with 4 sacks of cement. The casing was cut off at 3000' and pulled at 880'. Mike Kelso called Dist #2 office and requested to plug at 850' where casing was pulled apart. Doug Louis gave permission to plug at 850'. Spotted 70 sacks of cement at 850'. Circulated cement from 380' - 0'.

60/40 posmix with 4% gel

Allied Cement #23160

Perfs:

Top	Bot	Thru	Comments
4436	4444		

**RECEIVED
KCC DISTRICT #2
FEB 21 2006
WICHITA, KS**

INVOICED

Remarks:

Plugged through: TBG

JATE 3-1-06
INV. NO 2006061210

District: 02

Signed [Signature]
(TECHNICIAN)

RECEIVED
MAR 01 2006
KCC WICHITA