

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-03992-00-00

Spot: NESESW

Sec/Twnshp/Rge: 2-21S-7W

990 feet from S Section Line, 2970 feet from E Section Line

Lease Name: LEONARD

Well #: 2

County: RICE

Total Vertical Depth: 3383 feet

Operator License No.: 31925 •

Op Name: QUALITY WELL SERVICE, INC.

Address: 401 WEST MAIN  
LYONS, KS 67554

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3376		
SURF	8.625	107		

95  
\$ 109-

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/18/2006 12:15 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Revd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 727-3410

Proposed  
Plugging  
Method:

See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER

WitnessType: PARTIAL

Date/Time Plugging Completed: 01/18/2006 2:30 PM

KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

Perfs:

Sanded open hole to 3330' and capped with 5 sacks of cement. Cut off casing at 1350'. Pulled casing to 1050' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 600' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 200' and circulated cement to surface.

60/40 posmix with 4% gel

United Cement #6752

**RECEIVED**  
**KCC DISTRICT #2**  
**FEB 18 2006**  
**WICHITA, KS**

Remarks:

Plugged through: CSG

**INVOICED**

DATE 3-1-06  
TIME 2006061212

District: 02

Signed

*Virgil Clothier*

(TECHNICIAN)

**RECEIVED**  
**MAR 01 2006**  
**KCC WICHITA**